Connector Heights

INTERSTATE 5 / CALIFORNIA 56 INTERCHANGE PROJECT

West to North Connector
(Direct Connector, Hybrid, & Hybrid w/ Flyover Alts.)
The proposed Connector Height is 33 ft above the Carmel Valley Rd Northbound on-ramp.
"Connector High Point"

South to East Connector
(Direct Connector Alt. only)
The proposed Connector Height at this point is 24ft above Interstate 5

West to North Connector
(Direct Connector, Hybrid, & Hybrid w/ Flyover Alts.)
The proposed Connector Height is 37ft above Carmel Valley Rd.

South to East Connector
(Direct Connector Alt. only)
The proposed Connector Height at this point is 41ft above Interstate 5

South to East Connector
(Direct Connector Alt. only)
The proposed Connector Height at this point is 45ft above Interstate 5.
"Connector High Point"

South to East Connector
(Direct Connector Alt. only)
The proposed Connector Height is 28ft above existing NE Connector

South to East Connector
(Direct Connector Alt. only)
The proposed Connector Height is 22ft above existing WS Connector

POINTE DEL MAR WAY
PORTOFINO CIR.

Legend:
- Proposed Structures
- Proposed Widening & Improvements

SE Connector Ramp — 12'
Connector Height above I-5
Interstate 5
(approx. 63-72ft above sea level)
Not to Scale

SE Connector Ramp — 12'
Connector Height above Existing Connector Ramps
WS or NE Existing
Not to Scale

WN Connector Ramp — 12'
Connector Height above Carmel Valley Rd.
Carmel Valley Road
(approx. 36 above sea level)
Not to Scale

NORTH
No Scale